BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2016-17/RD/WORK_INDENT24252

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/20/2016-17, Date: 12.01.2017

Repairs and maintenance to existing borewells in Lottegollahalli, devinagara, muneshwaranagara, LKR nagara and surroundings ward no. 8, kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Hosahalli Jaganath Sanjay Reddy	
				In Figures	In Words
1	17	Lifting of Submersible pump set as per Soecification and direction etc complete as per specifications and directions of engineer in charge of the work	Each	800.0	Rupees Eight Hundred Only
2	17	Transportation of pumping machineries etc complete as per specifications and directions of engineer in charge of the work	Each	850.0	Rupees Eight Hundred Fifty Only
3	17	Labour charges (over hauling) etc complete as per specifications and directions of engineer in charge of the work	Job	500.0	Rupees Five Hundred Only
4	5	A) Repairs to Motor: Rewinding of submersible pump sets with copper insulation wire of suitable gauge as per ISI specification with guarantee of 6 months. (Above 10 HP upto 20 HP add Rs.150/- for every ½ HP) up to 10 HP etc complete as per specifications and directions of engineer in charge of the work 10 HP	No.	3650.0	Rupees Three Thousand Six Hundred Fifty Only
5	12	12.5 HP	No.	4700.0	Rupees Four Thousand Seven Hundred Only
6	17	Starter (with one year Guarantee) etc complete as per specifications and directions of engineer in charge of the work	No.	5000.0	Rupees Five Thousand Only
7	17	Rotor (with one year Guarantee) etc complete as per specifications and directions of engineer in charge of the work	No.	4650.0	Rupees Four Thousand Six Hundred Fifty Only
8	17	Upper Flange etc complete as per specifications and directions of engineer in charge of the work	No.	300.0	Rupees Three Hundred Only
9	17	Lower Housing etc complete as per specifications and directions of engineer in charge of the work	No.	600.0	Rupees Six Hundred Only
10	17	Carbon Housing etc complete as per specifications and directions of engineer in charge of the work	No.	450.0	Rupees Four Hundred Fifty Only
11	17	Thrust bearing block assembly complete with Segment bearing pad etc complete as per specifications and directions of engineer in charge of the work	No.	1100.0	Rupees One Thousand One Hundred Only
12	17	Oil Seal etc complete as per specifications and directions of engineer in charge of the work	No.	100.0	Rupees One Hundred Only
13	17	Oil Seal Steel Bush etc complete as per specifications and directions of engineer in charge of the work	No.	100.0	Rupees One Hundred Only
14	255	Guide vane etc complete as per specifications and directions of engineer in charge of the work	No.	150.0	Rupees One Hundred Fifty Only
15	255	Impeller Shell moulded with aluminium Bronze) etc complete as per specifications and directions of engineer in charge of the work	No.	420.0	Rupees Four Hundred Twenty Only
16	17	Discharge outlet (D.O) Bearing D.O Steel Bush etc complete as per specifications and directions of engineer in charge of the work	No.	400.0	Rupees Four Hundred Only
17	17	Steel Bush etc complete as per specifications and directions of engineer in charge of the work	No.	120.0	Rupees One Hundred Twenty Only
18	17	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) etc complete as per specifications and directions of engineer in charge of the work	No.	900.0	Rupees Nine Hundred Only
19	17	Non – return valve (NRV) assembly complete with rubber 'O' Ring etc complete as per specifications and directions of engineer in charge of the work	No.	1300.0	Rupees One Thousand Three Hundred Only
20	17	Cable Guard etc complete as per specifications and directions of engineer in charge of the work	No.	100.0	Rupees One Hundred Only
21	17	Brass Filter etc complete as per specifications and directions of engineer in charge of the work	No.	200.0	Rupees Two Hundred Only
22	17	Re-erection charges of pumping machineries including overhauling and pointing etc complete as per specifications and directions of engineer in charge of the work	Each	900.0	Rupees Nine Hundred Only

E.E. (BTP. DIV)

08/03

	roved Qty.	Description	Unit	Approved Tender Rates of Hosahalli Jaganath Sanjay Reddy	
				In Figures	In Words
23	265	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 Volts. P. No. 49/ I No. 29-b(1) 4 Sqm mm of 56 strands 0.3mm dia Group - A etc complete as per specifications and directions of engineer in charge of the work	Mtr	123.5	Rupees One Hundred Twenty Three and Fifty Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

08/03